

Rozbudowa szpitala w Puszczykowie								Nr rysunku		strona: 1/x	
WIEŃCE ŻELBETOWE								K-10			
Nr Pręta	Średnica	Długość	Ilość	Długość w [m] dla średnic Stal A-I				Długość w [m] dla średnic Stal A-IIIIN			
	[mm]	[m]	[szt]	4,5	6	8	10	12	16	20	25
wieńce stropu nad piwnicą											
W3-1	12	11,60	2					23,20			
W2-1	12	44,65	4					178,60			
W2-3	6	0,84	180		151,20						
W2-1	12	62,65	4					250,60			
W2-3	6	0,84	252		211,68						
W1-1	12	43,59	6					261,54			
W1-2	6	1,04	350		364,00						
W1-1	12	45,15	6					270,90			
W1-2	6	1,04	362		376,48						
W1-1	12	50,80	4					203,20			
W1-2	6	1,04	204		212,16						
W1-1	12	34,92	4					139,68			
W1-2	6	1,04	140		145,60						
W1-1	12	12,70	4					50,80			
W1-2	6	1,04	52		54,08						
W1-1	12	11,65	4					46,60			
W1-2	6	1,04	47		48,88						
W1-1	12	8,65	6					51,90			
W1-2	6	1,04	70		72,80						
4	12	1,20	76					91,20			
6	12	1,95	8					15,60			
1a	12	1,60	2					3,20			
1a	12	1,45	4					5,80			
1a	12	1,25	2					2,50			
2a	6	1,56	51		79,56						
2b	6	1,36	51		69,36						
7	12	1,00	48					48,00			
wieńce stropu nad parterem											
W1-1	12	153,95	4					615,80			
W1-2	6	1,04	611		635,44						
W1-1	12	81,05	6					486,30			
W1-2	6	1,04	648		673,92						
W2-1	12	34,95	4					139,80			
W2-3	6	0,84	138		115,92						
W3-1	12	23,30	2					46,60			
W3-5	6	0,27	154		41,58						
W4-1	12	87,75	4					351,00			
W4-8	6	0,70	351		245,70						
4	12	1,20	8					9,60			
6	12	1,95	8					15,60			
7	12	1,00	40					40,00			
wieńce ściany attykowej											
W4-1	12	120,62	4					482,48			
W4-8	6	0,70	482		337,40						
Razem długość			[m]		3835,8			3830,5			
Masa 1mb			[kg]	0,125	0,222	0,395	0,617	0,888	1,578	2,466	3,853
Razem masa dla 1 elem.			[kg]		851,4			3400,8			
OGÓŁEM dla 1 elem.			[kg]	851,4				3400,8			
dodano 5% na zakłady			[kg]		893,9			3570,8			
OGÓŁEM dla 1 elem.			[kg]	893,9				3570,8			